BROOKVALE ROAD

BROOKVALE DOWNS

RATHFARNHAM ROAD

BROOKVALE ROAD

GRANNAGH ROAD

RATHFARNHAM PARK

DODDER PARK ROAD

RATHFARNHAM PARK

REMOVE EXISTING 1.5M MANDATORY CYCLE TRACK

DROPPED KERB WITH BUFF TACTILE PAVING

PROPOSED RAISED TABLE ENTRY TREATMENT WITH BUFF TACTILE PAVING

PROPOSED SIGNAL CONTROLLED PEDESTRIAN CROSSING

EXISTING UPGRADED BUS STOP

EXISTING UPGRADED BUS STOP

EXISTING UPGRADED BUS STOP

DROPPED KERB WITH BUFF TACTILE PAVING

EXISTING BUS LANE EXTENDED TO JUNCTION

ALL PEDESTRIAN SIGNALS TO BE UP GRADED

Section 001

EXISTING SECTION DETAIL

3.10 2.90 3.40 4.40

PROPOSED SECTION DETAIL

3.20 3.00 3.00 4.60

QUALITY BUS NETWORK PROJECT OFFICE
Oifig Thionscadal an Ghréasán Bus

Verizon Building,
4th Floor,
Lower Erne Street,
Dublin 2.

Tel : + 353 (1) 6860100
Fax : +353 (1) 6860127
Web : www.dublincity.ie

M. Phillips
DIRECTOR OF TRAFFIC & CITY ENGINEER, DUBLIN CITY COUNCIL.
J. Walsh
DIRECTOR OF TRANSPORTATION & COUNTY ENGINEER, SOUTH DUBLIN COUNTY COUNCIL
A. McElligott
PROJECT MANAGER, QBN PROJECT OFFICE

NDP
National Development Plan
Transforming Ireland

Údarás
Náisiúnta Iompair
National Transport Authority

Dublin City Council
Comhairle Cathrach Átha Cliath

Comhairle Contae
Átha Cliath Theas
South Dublin County Council

LEGEND

EXISTING BUS LANE
PROPOSED BUS LANE
EXISTING CYCLE LANE
PROPOSED CYCLE LANE
CARRIAGEWAY
BUS STOP
PROPOSED PATH
EXISTING LOADING BAY
LUAS LINE
RAISED ENTRY TREATMENT
TRAFFIC ISLAND
VERGE
PARKING
TAXI RANK

© Ordnance Survey Ireland. All rights reserved. Licence Number
2010/22/CCMA Dublin City Council

No.	Revision	Date	By	Chk'd	App'd
	Stage		Date		App'd

PRELIMINARY
APPROVAL
TENDER
CONSTRUCTION

Project Title
RATHFARNHAM QBC ENHANCEMENTS

Drawing Title
RECOMMENDED SCHEME

Designed:	PMN / SS	CAD File:	T-QBN-116	Sheet
Drawn:	DM	Job No:	116	004 \ 019
Checked:		Scale:	1:500 @ A1 / 1:1000 A3	Drawing No:	Rev:
Approved:		Date:	JANUARY 2011	T-QBN-116-DRS-004	

P:T QBN 116 \DGN\LAYOUT_FILES_3_A_RECOMMENDED_SCHEME