



NOTES
 It is the contractors responsibility to check design levels and sizes for compliance. Any discrepancies or errors to be identified to the design team.

New Synthetic Area
 Length - 100.0m
 Width - 60.0m
 + Recesses

Total Area - 6,122m²

Football Line Markings
 In-laid White (FIFA Quality).
 Length - 92.0m
 Width - 52.0m

Rugby Line Markings
 (Training Only - no permanent goalposts)
 In-laid, White.

Length - 80.0m
 + In-goal Areas - 6.0m
 Width - 52.0m

Cross-field Markings (Painted Blue).

Length - 52.0m
 Width - 92m/ 3
 Penalty Areas - 12.0m x 6.0m

- KEY**
- Site Boundary
 - New Synthetic turf
 - New hardstanding/ access path
 - New 5.0m high perimeter fencing
 - New 1.2m high spectator fencing
 - M New Double Gate
 - New Detox Area
 - S1 New Floodlighting Column
 - Existing Road/ Footpath Network
 - T Existing Trees
 - NT New Trees (copse, native)

School

REVISION	DETAILS	BY	DATE	CHECKED



**TALLAGHT 3G
 GENERAL ARRANGEMENT
 NEW 3G PITCH**



Date: 04/2021 Scale: 1:500 @ A3	Job No. 2936	Drawn by: FG Checked by: DD
------------------------------------	--------------	--------------------------------