



KEY

Site extents approx. 2.95ha (7.3acres)

Existing contours at 0.50m interval

New footpath asphalt, 2.0m wide

Existing footpath resurfaced as required

Bow-top railing to existing or new boundary stub wall

Possible land ownership transfer (subject to Council agreement)

Feature entrance areas with walls, seats and block paving (subject to detailed design)

Activity Circuit (100m markers) with exercise equipment and/or natural play features

Children's natural play area

Kissing gate or similar new or refurbished

New footbridge crossing steel truss or similar construction

Existing footbridge crossing retained and refurbished

Additional streetlights

Formal signature trees (semi-mature)

Informal groups of selected standard native trees

Native hedgerow

Wildflower grassland (through changed management practice) with native bulbs

Regularly cut grass

Notes:

1. This Drawing to be read in Conjunction with all Relevant Specifications & Engineering Drawings

2. This drawing is to be used for the Design Element Identified. All other information Shown on the Drawing is to be considered as Indicative only

3. The Contractor shall confirm the Location of all Underground and Overhead Utilities before Excavation Commences

4. All Works shall be confirmed by the Employer's Representative prior to Commencement of Works

5. The Employer's Representative shall be Notified by the Contractor of any Errors or Omissions

1050

500

0

500

1000

GRAPHIC SCALE (metres)

03	15/07/22	HAR	NDJ	NDJ
Issued for Part 8 Planning				
02	15/07/22	HAR	NDJ	NDJ
Issued for Discussion				
01	01/07/22	HAR	NDJ	NDJ
Issued for Discussion				
Issue	Date	By	Chkd	Appd

Client

South Dublin County Council

Job Title

Whitestown Stream Local Park Up-grade Tallaght, Dublin 24

Scale 1:500 at A1

Discipline

Nicholas de Jong Associates

URBAN DESIGN

Drawing Title

DETAILED LAYOUT PLAN Sheet 2

Drawing Status

Part 8 Planning

Job No

2205

Drawing No

L-005

Issue

R3

Do not scale